BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

SCHDULE-B

Name of Work:Improvements to roads and drains at 2nd main & 7th cross Manjunatha Nagara in Ward No 14 (Bagalagunte)

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in **Ordinary soil** involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	1285.32	86.92	Rupees Eighty six & Ninty Two Paise Only
2	Providing and laying in position **plain cement concrete of mix 1:4:8** with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	32.22	5159.02	Rupees Five Thousand One hundred Fifty Nine & Two Paise Only
3	Providing and removing **centering,** shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications,	Sqm	716.00	310.58	Rupees Three hundred ten & Fifty Eight Only
4	Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008- i) Upto 5 m height.	Cum	67.12	6965.26	Rupees Six thousand nine hundred Sixty Five & Twenty Six Only
5	Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specifications	Tonne	5.32	66482.14	Rupees Sixty Six thousand four hundred Eighty two & Fourteen Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive engineer

6	Supplying and fixing **precast** rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm	161.10	1698.00	Rupees One thousand Six hundred Ninty Eight Only
7	Providing and fixing Pre cast solid concrete kerb stones made out of No.272.21 CC 1:2:4 with top and bottom width 114 and 165mm respectively, 400mm high and 450mm in length finished with CM1:3 plastering and finishing cutting including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, leads and lifts etc., complete as per the direction of Engineer-in-charge of the work	No	889.00	331.78	Rupees Three hundred Thorty One & Seventy Eight Paise Only
8	For Grading I material construction of granular sub-base by providing coarse graded crushed stone aggregates of Granite/ trap/basalt material spreading in uniform layers with motir grader on prepared surface mixing by a mix in place method with rotawater at OMC, and Compacting with vibratory roller to achieve the desired density, complete as per specifications.by mix in a Place method for course Graded Granular Sub Base Material as per 400-2 for grading I material	Cum	273.00	1518.98	Rupees One Thousand Five hundred & Eighteen & Ninty Eight Paise Only
9	Providing, laying, spreading and compacting graded stone aggregates to **wet mix macadam** specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Cum.	627.90	1768.08	Rupees One thousand Seven hundred Sixty Eighy & Eight Paise Only
10	Providing and applying primer coat with S.S. Bitumen emulsion on prepared surface of granular base such as WBM, WMM including clearing of road surface and spraying primer at the rate of 0.6 kg / sqm using mechanical means complete as per specifications, with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work	Sqm	2730.00	27.56	Rupees Twenty Seven & Fifty Six Paise Only
11	Providing and applying tack coat on the prepared black topped surfaces at 5kg per 10 sqm, heating bitumen in boiler fitted with spray set (Excluding cleaning of road surface) including cost of all Materials, labour, HOM of machineries complete as per specifications.		2730.00	11.66	Rupees Eleven & Sixty Six Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive engineer

12	providing and laying bituminous concrete with hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder and filter transporting the hot mix to work site laying with paver finisher to the required grade, level and alignment. rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction as per MORTH Speicification clause no 500.9 complete in all respects complete as per specification no 509. using 40/60 TPH Capacity H.M.P With Mechanical paver Gr-II (30 mm to 45 mm) with 6% VG-30 Bitumen	Cum	122.85	7083.98	Rupees Seven Thousand Eighty Three & Ninty Eight Paise Only
13	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	1285.32	85.65	Rupees Eighty Five & Sixty Five paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer